



QUOTE #52

SENT ON:

RECIPIENT:

Chris Johnson

111 East Maple Avenue
Independence, Missouri 64050

Customer Name: City of Independence

Job Title: Independence Water - Dodgion

5700 Merriam Drive
Merriam, Kansas 66203

Phone: (913) 962-8083

Email: kreinoehl@etikc.com

Website: www.etikc.com

PRODUCT / SERVICE	DESCRIPTION	QTY.	UNIT PRICE	TOTAL
AXIS P3719-PLE	AXIS P3719-PLE Network Camera is a compact 15-megapixel camera with four varifocal lenses (4 x Quad HD) enabling overview and detailed surveillance. With one IP address and one network cable, the four-cameras-in-one unit provides a flexible, cost-effective solution for multidirectional surveillance. 360° IR illumination, WDR and Lightfinder technology provides excellent video quality in any light conditions. Each camera head can be individually positioned (pan, tilt, roll, and twist) along a circular track. Remote zoom and focus makes it easy to install and the clear cover, with no sharp edges, ensures undistorted views in all directions. The camera has an integrated weathershield.	1	\$1,359.15	\$1,359.15
AXIS T94N01D PENDANT KIT	AXIS T94N01D Pendant Kit comprises a weathershield and a mounting adapter for AXIS P3717-PLE Network Camera. The mounting adapter is compatible with 1.5-inch NPS thread. The kit enables AXIS P3717-PLE to be mounted on walls, poles, parapets and outer corners using AXIS T91 mounting accessories.	1	\$75.65	\$75.65
AXIS T91D61 WALL MOUNT	Chromated and powder coated aluminum wall mount with 1.5" NPS thread for fixed dome pendant kits. Cable routing from behind or through 3/4" conduit hole on the side. Includes mounting plate, pipe seal and conduit hole cover. Color: White	1	\$71.40	\$71.40
AXIS ACI CONDUIT ADAPTER 1/2"-3/4" A	Step up ACI adapter for attaching 3/4" conduits or M25 pipes to AXIS products with a 1/2" conduit interface such as AXIS P32-V series (requires AXIS ACI conduit bracket B) and AXIS Q3505-V. 2 pcs	1	\$33.15	\$33.15

SENT ON:

PRODUCT / SERVICE	DESCRIPTION	QTY.	UNIT PRICE	TOTAL
Custom Plate	Custom plate for AXIS T91D61 Wall Mount to secure mount to I-Beam with Minerallac 703 Beam Clamps	1	\$40.00	\$40.00
MINERALLAC 1/2 - 13 BEAM CLAMP	1/2-13 Beam Clamp, Up To 7/8" Flange, 1/2"-13 Tapped Holes Bottom & Back Of Beam Clamp, Malleable Iron	4	\$10.00	\$40.00
3/4 in. x 10 ft. Electrical Metallic Tube (EMT) Conduit	3/4 in. x 10 ft. Electrical Metallic Tube (EMT) Conduit	2	\$19.23	\$38.46
3/4 in. Electrical Metallic Tube (EMT) Set-Screw Connector	3/4 in. Electrical Metallic Tube (EMT) Set-Screw Connector	1	\$1.00	\$1.00
3/4 in. Universal Strut Pipe Clamp - Silver Galvanized	3/4 in. Universal Strut Pipe Clamp - Silver Galvanized	1	\$3.20	\$3.20
Cat6E Plenum Network Cable	23 AWG, 4 Pair, Category 6 Enhanced 550 MHz Plenum, Orange	20	\$0.41	\$8.20
PROFESSIONAL INSTALLATION	Hourly labor charge for cable & hardware installation.	16	\$97.00	\$1,552.00
PROFESSIONAL SERVICES	Hourly labor charge for software & network configuration.	2	\$130.00	\$260.00
GSC-OM-E-1C	Genetec - 1 camera connection	1	\$200.00	\$200.00
ADV-CAM-E-5Y	Genetec™ Advantage for 1 Omnicast™ Enterprise Camera - 5 years	1	\$143.20	\$143.20

Total **\$3,825.41**

Scope of Work:

Electronic Technology, Inc. will install an AXIS P3719-PLE Quad HD Dome on the water tower I-beam that also holds the tower ladder. ETI will secure the camera to the I-beam and adjust each sensor to cover areas as defined in the attached camera layout drawing.

EMT conduit will be installed to protect Cat6 network cable installed within the conduit. The cable drop will land in the existing data cabinet.

- Quote assumes PoE Class 3 ports are available in the data cabinet.
- Quote assumes video is being transmitted via an existing network to an existing server with space for video data storage.



QUOTE #52

SENT ON:

Notes Continued...

Quote valid for 30 days.
Tax is not included.
NET 30 Terms.

Signature: _____ Date: _____