

February 7, 2023

Mr. Bob Parks  
17221 East 23rd Street South  
Independence, MO 64057

RE: 39<sup>th</sup> Street Reservoir

Dear Mr. Parks:

Upon inspection of the beams on the interior roof of the above referenced tank, Worldwide Industries Corp. recommends that the following *additional* number of deteriorated beams be replaced:

- Scope of work for deteriorated beams:
  - Remove and dispose of deteriorated beam
  - Purchase new beam
  - Shop blast new beam to an SSPC-SP10
  - Apply zinc primer to new beam
  - Apply two coats of N140 to new beam
  - Abrasive blast interior roof where deteriorated beam was removed to an SSPC-SP10
  - Apply zinc primer to prepared roof area
  - Apply two coats of N140 to prepared roof area
  - Install new shop coated beam
  - After all interior roof structures have been repaired or replaced, we would apply a finish coat of FC22 to roof area and any new beams
- One additional C4x5.4 channel member to be replaced with C7x9.8 channel member, our price is \$6,415.00 per beam. This price includes the above scope of work, new crutch plates, and hardware.  
1 additional beam x \$6,415.00 = **\$6,415.00**
- For the intermediate (middle) set of C7x9.8 channel members to be replaced, Worldwide Industries' price is \$7,090.00 per beam. This price includes the above scope of work, new crutch plates, and hardware.  
20 additional beams x \$7,090.00 = **\$141,800.00**
- For the outer set of C9x13.4 channel members to be replaces, Worldwide Industries' price is \$7,620.00 per beam. This price includes the above scope of work, new crutch plates, and hardware.  
36 additional beams x \$7,620.00 = **\$274,320.00**
- Any additional beams deemed necessary will be done on a per beam basis.

**PROTECTION THAT GOES BEYOND THE SURFACE**

- All work to be completed by May 1, 2023, with the exception of the intermediate and finish coat on the exterior roof.
- It will be required that we can work on Saturdays, with quiet work on Sundays.
- I have attached pricing for the utilization of heat and dehumidification for any days needed for this tank. I would highly recommend that you spend the additional money for this rental, as this would absolutely ensure that the tank can be put back into service by May 1, 2023.

**GRAND TOTAL (without Heat & DH) = \$422,535.00**

Please forward a change order in this amount as soon as possible.

If you have any questions or comments, please feel free to contact me at any time.

Sincerely,

A handwritten signature in black ink, appearing to read "John H. Chamberlain", written over a horizontal line.

John H. Chamberlain  
Vice President  
Worldwide Industries Corp.